


PHOTOGRAPH SHEET - TP29

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



TP29_11-31-06



TP29_11-31-43

TEST PIT LOG - TP30

Client:

Project: Farrar West Development

Location: Farrar, Palmerston

Project ID: DAR2026-0015

Date: 07/07/2026



1:20

Sheet 1 of 1

Logged by: NB

Position: E.1718290m N.2470736m

Plant: 5.5t excavator

Checked By:

Elevation: 19.592 m (mAHD)

Contractor: Arjays

Dimensions : 0.45m x 2.00m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Partide Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
	1.50	PP=320kPa	19.4	1		TOPSOIL: Sandy GRAVEL: fine grained, sub-angular to sub-rounded pale brown sand, fine to coarse grained, trace clay, low plasticity. ... from 0.00m to 0.20m, Some rootlets	D	L to MD	1			0.60-1.00m: DCP refusal at 0.6m and continued at 1.0m after excavation
					2							
					5							
					8							
					19.0		GP: Sandy GRAVEL: fine grained, sub-angular to sub-rounded pale brown sand, fine to coarse grained, trace clay, low plasticity. (ALLUVIUM)	VD	16			
									25			
	2.70	PP=290kPa	18.6	1		CI: CLAY: medium plasticity, orange brown mottled white trace gravel, fine grained, trace sand, fine grained. (RESIDUAL).	≈PL	F	2			
									2			
									2			
									3			
									8			
			17.0			CI: Gravelly CLAY: medium plasticity, white mottled orange brown; gravel, fine to coarse; trace sand, fine; (EXTREMELY WEATHERED MATERIAL)		St to VSt				
			16.6	3		Test pit terminated at 3.00 m						

DCP Equipment Ref.:	In Situ Vane Equipment Ref.:	Pocket Penetrometer Equipment Ref.:
Termination Reason: Target Depth		
Remarks:		
This report must be read in conjunction with accompanying notes and abbreviations.		

PHOTOGRAPH SHEET - TP30

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



TP30_14-32-28



TP30_14-33-23

CMW Geosciences
Great People | Practical Solutions


Sheet 1 of 1

Dimensions : 0.45m x 2.00m

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP31

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



TP31_08-29-14



TP31_08-29-44

CMW Geosciences
Great People | Practical Solutions

Sheet 1 of 1

Dimensions : 0.45m x 2.00m

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP32

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



TP32_10-32-15



TP32_10-32-55

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP33

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



TP33_13-42-41



TP33_13-43-26

TEST PIT LOG - TP34

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



1:20 Sheet 1 of 1

Logged by: NB Position: E.1718292m N.2470823m Plant: 5.5t excavator
Checked By: Elevation: 20.074 m (mAHD) Contractor: Arjays Dimensions : 0.45m x 2.00m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Particle Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
			19.9			GP: TOPSOIL : Sandy GRAVEL: fine grained, sub-angular to sub-rounded pale brown sand, fine to coarse grained, trace clay, low plasticity. (NATURAL) ... from 0.00m to 0.20m, trace rootlets GP: Sandy GRAVEL: fine grained, sub-angular to sub-rounded pale brown sand, fine to coarse grained, trace clay, low plasticity. (NATURAL)	D	MD	8			
									5			
									5			
								VD	14			
									18			
									17			
			19.4						14			
						LATERISED SILTSTONE: fine, orange brown, highly weathered, medium to high strength, dry			13			
									15			
				1					20			
									25			
												1.00-1.10m: DCP Refusal
			18.7			Test pit terminated at 1.40 m						
				2								
				3								


DCP Equipment Ref.:	In Situ Vane Equipment Ref.:	Pocket Penetrometer Equipment Ref.:
Termination Reason: Practical refusal		
Remarks:		
This report must be read in conjunction with accompanying notes and abbreviations.		

PHOTOGRAPH SHEET - TP34

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 07/07/2026



TP34_15-21-25



TP34_15-22-15

TEST PIT LOG - TP35

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 08/07/2026



1:20 Sheet 1 of 1

Logged by: NB Position: E.1718269m N.2470938m Plant: 5.5t excavator
Checked By: Elevation: 20.9848 m (mAHD) Contractor: Arjays Dimensions : 0.45m x m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Particle Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
				20.8		TOPSOIL: Silty SAND: fine to coarse grained, pale grey brown silt, low plasticity. ... from 0.00m to 0.20m, trace rootlets	D	MD	5	11		
						LATERISED SILTSTONE: fine, orange brown, highly weathered, low strength, dry				25		0.20-1.00m: DCP refusal at 0.2 m and continued at 1.0 m after excavation
	0.9 - 1.0	TP35_01 D		20.3		GC: Clayey GRAVEL: fine grained, angular to sub-angular pale orange brown; clay, low plasticity, with sand, fine to coarse grained. (RESIDUAL)	M					
				1				L	3			
									3			
				19.6		GP: GRAVEL: fine to coarse grained, angular to sub-angular, red orange brown; with clay, low plasticity, trace sand, fine to coarse grained. (RESIDUAL)	M		3			
				19.1								
				19.0		PHYLITE: fine, red brown mottled yellow, amorphous, moist, moderately weathered, low to medium strength. ... from 1.90m to 2.00m, BURRELL CREEK FORMATION Test pit terminated at 2.00 m						
				2								
				3								


DCP Equipment Ref.:	In Situ Vane Equipment Ref.:	Pocket Penetrometer Equipment Ref.:
Termination Reason: Practical refusal		
Remarks:		
This report must be read in conjunction with accompanying notes and abbreviations.		

PHOTOGRAPH SHEET - TP35

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 08/07/2026



TP35_08-32-51



TP35_08-34-11

TEST PIT LOG - TP36

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 08/07/2026



1:20 Sheet 1 of 1

Logged by: NB Position: E.1718127m N.2471065m Plant: 5.5t excavator
Checked By: Elevation: 22.3756 m (mAHD) Contractor: Arjays Dimensions : 0.45m x 2.00m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Particle Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
▼			22.2			TOPSOIL : Clayey SAND: fine to coarse, dark brown; clay, low plasticity; trace gravel, fine grained	M	L 3 D to VD	2			
						GW: GRAVEL: fine to coarse grained, angular to sub-angular orange brown mottled white; with clay, low plasticity, with sand, fine to coarse grained.(EXTREMELY WEATHERED MATERIAL)			1			
									3			
										12		
			21.8			LATERISED SILTSTONE: fine, orange brown, moderately weathered, medium strength, wet				25		
			21.7			Test pit terminated at 0.70 m						
				1								
				2								
				3								

DCP Equipment Ref.: In Situ Vane Equipment Ref.: Pocket Penetrometer Equipment Ref.:

Termination Reason: Practical refusal

Remarks:

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP36

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 08/07/2026



CMW Geosciences
Great People | Practical Solutions


Sheet 1 of 1

Dimensions : 0.45m x 2.00m

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP37

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 10/07/2026



CMW Geosciences
Great People | Practical Solutions

1:20 Sheet 1 of 1

Dimensions : 0.45m x 2.00m

1.00-1.10m: DCP refusal –

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP38

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 09/07/2026



TP38_12-39-13



TP38_12-39-39

CMW Geosciences
Great People | Practical Solutions

Sheet 1 of 1

Dimensions : 0.45m x 2.00m

This report must be read in conjunction with accompanying notes and abbreviations.

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP39

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 09/07/2026



TP39_13-40-59



TP39_13-41-31

TEST PIT LOG - TP40

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 10/07/2026



1:20 Sheet 1 of 1

Logged by: NB Position: E.1717754m N.2471274m Plant: 5.5t excavator
Checked By: Elevation: 28.3208 m (mAHD) Contractor: Arjays Dimensions : 0.45m x 2.00m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Particle Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
	0.4 - 0.5	TP40_01 D	28.1			TOPSOIL : Sandy CLAY: low plasticity, dark brown ; sand, fine to coarse grained; with gravel, fine grained ... from 0.00m to 0.30m, some rootlets	<PL	S to F	1			
						CL: Sandy CLAY: low plasticity, dark brown; sand, fine to medium grained; trace gravel, fine grained. (ALLUVIUM)			2			
									2			
									3			
									5			
			27.7			LATERISED SILTSTONE: fine, orange brown mottled yellow white, highly weathered, low strength, moist			11			1.00-1.10m: DCP refusal
									20			
									16			
									13			
									25			
			1			... from 1.10m to 1.80m, recovered as sandy GRAVEL trace clay						
			26.5			Test pit terminated at 1.80 m						
			2									
			3									

DCP Equipment Ref.: In Situ Vane Equipment Ref.: Pocket Penetrometer Equipment Ref.:

Termination Reason: Practical refusal

Remarks:

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP40

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 10/07/2026



TP40_12-24-57



TP40_12-26-41


TEST PIT LOG - TP41

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 09/07/2026



1:20 Sheet 1 of 1

Logged by: NB Position: E.1717581m N.2471224m Plant: 5.5t excavator
Checked By: Elevation: 33.866 m (mAHD) Contractor: Arjays Dimensions : 0.45m x 2.00m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Particle Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
			33.7		TOPSOIL : Silty SAND: fine to coarse grained, pale brown grey; silt, low plasticity, trace gravel, fine grained GC: Clayey GRAVEL: fine to coarse grained, angular to sub-angular; brown, clay, low plasticity, with sand, fine to coarse grained.(RESIDUAL)	D	VD	2				0.60-0.70m: DCP refusal
									20			
									14			
									14			
									25			
									22			
			33.2		LATERISED SILTSTONE: fine, orange brown mottled yellow, Distinctly weathered, medium to high strength, dry							
			1									
			32.8		Test pit terminated at 1.10 m							

DCP Equipment Ref.: In Situ Vane Equipment Ref.: Pocket Penetrometer Equipment Ref.:

Termination Reason: Pratical Refusal

Remarks:

This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP41

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 09/07/2026



TP41_07-44-12



TP42_16-01-32

TEST PIT LOG - TP42

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 08/07/2026



1:20 Sheet 1 of 1

Logged by: NB Position: E.1717373m N.2471226m Plant: 5.5t excavator
Checked By: Elevation: 40.6012 m (mAHD) Contractor: Arjays Dimensions : m x 2.00m

Groundwater	Samples & Insitu Tests		RL (m)	Depth (m)	Graphic Log	Material Description Soil Type, Plasticity or Particle Characteristics, Colour, Secondary and Minor Components	Moisture Condition	Consistency/ Relative Density	Dynamic Cone Penetrometer (Blows/100mm)			Structure & other observations
	Depth	Type & Results							5	10	15	
			40.4			TOPSOIL : Silty SAND: fine grained, pale brown fines, fine grained, trace gravel, fine grained ... from 0.00m to 0.20m, some rootlets			6			
						MIXTURE OF COBBLES/BOULDERS AND SOIL: 40% cobbles , clast supported, angular to sub-angular, orange brown mottled white; gravel, fine to coarse grained, with sand, fine to coarse grained. (RESIDUAL)	D	VD		25		
			39.9			PORCELLENITE : fine, red brown mottled white yellow, amorphous, dry, moderately weathered, high strength.						
			39.8			Test pit terminated at 0.80 m						
				1								
				2								
				3								

DCP Equipment Ref.: In Situ Vane Equipment Ref.: Pocket Penetrometer Equipment Ref.:
Termination Reason: Practical refusal
Remarks:
This report must be read in conjunction with accompanying notes and abbreviations.

PHOTOGRAPH SHEET - TP42

Client:
Project: Farrar West Development
Location: Farrar, Palmerston
Project ID: DAR2026-0015
Date: 08/07/2026



TP42_16-00-59



TP42_16-01-32


APPENDIX C

Laboratory Test Certificates

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 1 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6841	Location	TP01
Client Reference	-		1.1
Sampling Method	AS1289.1.2.1 CI 6.4b		1.2
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 8/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH			
19.0		100					
13.2		100					
9.5		99					
6.7		92					
4.75		79					
2.36		62					
1.18		56					
0.425		52					
0.075		36					

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		32		0.075/0.425 Fines Ratio		0.69	
Plastic Limit (%)		13		PI x 0.425 Ratio (%)		995.6	
Plastic Index (%)		19		LS x 0.425 Ratio (%)		524.0	
Linear Shrinkage (%)		10.0		Particle Size Dist. Moisture Content (%)		14.4	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 2 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6842	Location	TP03
Client Reference	-		1.2
Sampling Method	AS1289.1.2.1 CI 6.4b		1.3
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 10/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH
19.0		100		
13.2		93		
9.5		89		
6.7		85		
4.75		78		
2.36		66		
1.18		57		
0.425		46		
0.075		32		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		45		0.075/0.425 Fines Ratio		0.70	
Plastic Limit (%)		22		PI x 0.425 Ratio (%)		1066.7	
Plastic Index (%)		23		LS x 0.425 Ratio (%)		487.0	
Linear Shrinkage (%)		10.5		Particle Size Dist. Moisture Content (%)		20.5	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		Form ID: W85MCRP Rev 2

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 3 of 18

Test Procedures	AS1289.3.6.1, AS1289.1.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6843	Location	TP08
Client Reference	-		0.3
Sampling Method	AS1289.1.2.1 CI 6.4b		0.4
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 10/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	Insitu
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
53.0		99		
37.5		97		
26.5		92		
19.0		91		
13.2		83		
9.5		79		
6.7		76		
4.75		72		
2.36		65		
1.18		57		
0.425		50		
0.075		39		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		32		0.075/0.425 Fines Ratio		0.78	
Plastic Limit (%)		21		PI x 0.425 Ratio (%)		553.3	
Plastic Index (%)		11		LS x 0.425 Ratio (%)		276.6	
Linear Shrinkage (%)		5.5		Particle Size Dist. Moisture Content (%)		13.6	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 4 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6845	Location	TP10
Client Reference	-		0.4
Sampling Method	AS1289.1.2.1 CI 6.4b		0.6
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH			
53.0		96					
37.5		89					
19.0		86					
13.2		81					
9.5		77					
6.7		71					
4.75		61					
2.36		40					
1.18		30					
0.425		27					
0.075		12					

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		26		0.075/0.425 Fines Ratio		0.45	
Plastic Limit (%)		12		PI x 0.425 Ratio (%)		375.3	
Plastic Index (%)		14		LS x 0.425 Ratio (%)		201.0	
Linear Shrinkage (%)		7.5		Particle Size Dist. Moisture Content (%)		9.2	
Shrinkage Observations	Cracking						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	Approved Signatory: Gurdeep Singh
			Form ID: W85MCRP Rev 2

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 5 of 18

Test Procedures	AS1289.3.6.1, AS1289.1.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6846	Location	TP13
Client Reference	-		0.1
Sampling Method	AS1289.1.2.1 CI 6.4b		0.3
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	Insitu
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
53.0		98		
37.5		91		
19.0		79		
13.2		68		
9.5		63		
6.7		60		
4.75		57		
2.36		46		
1.18		35		
0.425		29		
0.075		8		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		20		0.075/0.425 Fines Ratio		0.28	
Plastic Limit (%)		16		PI x 0.425 Ratio (%)		116.2	
Plastic Index (%)		4		LS x 0.425 Ratio (%)		87.1	
Linear Shrinkage (%)		3.0		Particle Size Dist. Moisture Content (%)		6.6	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 6 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6847	Location	TP14
Client Reference	-		1.6
Sampling Method	AS1289.1.2.1 CI 6.4b		1.7
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 8/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
53.0		95		
37.5		90		
26.5		86		
19.0		83		
13.2		72		
9.5		66		
6.7		60		
4.75		54		
2.36		44		
1.18		36		
0.425		28		
0.075		19		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		48		0.075/0.425 Fines Ratio		0.66	
Plastic Limit (%)		21		PI x 0.425 Ratio (%)		762.5	
Plastic Index (%)		27		LS x 0.425 Ratio (%)		310.7	
Linear Shrinkage (%)		11.0		Particle Size Dist. Moisture Content (%)		17.9	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		Form ID: W85MCRP Rev 2

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 7 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6848	Location	TP15
Client Reference	-		1.5
Sampling Method	AS1289.1.2.1 CI 6.4b		1.6
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH
19.0		100		
13.2		92		
9.5		87		
6.7		82		
4.75		77		
2.36		69		
1.18		60		
0.425		51		
0.075		41		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		43		0.075/0.425 Fines Ratio		0.80	
Plastic Limit (%)		22		PI x 0.425 Ratio (%)		1077.3	
Plastic Index (%)		21		LS x 0.425 Ratio (%)		590.0	
Linear Shrinkage (%)		11.5		Particle Size Dist. Moisture Content (%)		17.6	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 8 of 18

Test Procedures	AS1289.3.6.1, AS1289.1.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6849	Location	TP18
Client Reference	-		0.2
Sampling Method	AS1289.1.2.1 CI 6.4b		0.4
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	natural gravel (clayey with coffee rocks)
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
37.5		95		
19.0		91		
13.2		87		
9.5		83		
6.7		78		
4.75		71		
2.36		56		
1.18		45		
0.425		38		
0.075		22		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		26		0.075/0.425 Fines Ratio		0.57	
Plastic Limit (%)		18		PI x 0.425 Ratio (%)		307.5	
Plastic Index (%)		8		LS x 0.425 Ratio (%)		192.2	
Linear Shrinkage (%)		5.0		Particle Size Dist. Moisture Content (%)		11.3	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 9 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6850	Location	TP20
Client Reference	-		0.3
Sampling Method	AS1289.1.2.1 CI 6.4b		0.4
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH			
53.0		97					
37.5		91					
19.0		85					
13.2		79					
9.5		75					
6.7		72					
4.75		68					
2.36		60					
1.18		47					
0.425		39					
0.075		18					

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		20		0.075/0.425 Fines Ratio		0.44	
Plastic Limit (%)		14		PI x 0.425 Ratio (%)		236.7	
Plastic Index (%)		6		LS x 0.425 Ratio (%)		118.4	
Linear Shrinkage (%)		3.0		Particle Size Dist. Moisture Content (%)		8.3	
Shrinkage Observations	Cracking						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 10 of 18

Test Procedures	AS1289.3.6.1, AS1289.1.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6851	Location	TP22
Client Reference	-		0.2
Sampling Method	AS1289.1.2.1 CI 6.4b		0.4
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	natural gravel (silty with coffee rocks)
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
53.0		100		
37.5		97		
26.5		92		
19.0		89		
13.2		80		
9.5		75		
6.7		70		
4.75		64		
2.36		49		
1.18		36		
0.425		29		
0.075		9		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		28		0.075/0.425 Fines Ratio		0.32	
Plastic Limit (%)		16		PI x 0.425 Ratio (%)		352.5	
Plastic Index (%)		12		LS x 0.425 Ratio (%)		191.0	
Linear Shrinkage (%)		6.5		Particle Size Dist. Moisture Content (%)		8.9	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		Form ID: W85MCRP Rev 2

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 11 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6852	Location	TP24
Client Reference	-		2.6
Sampling Method	AS1289.1.2.1 CI 6.4b		2.8
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 10/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH
19.0		100		
13.2		89		
9.5		83		
6.7		76		
4.75		70		
2.36		61		
1.18		53		
0.425		44		
0.075		31		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		39		0.075/0.425 Fines Ratio		0.71	
Plastic Limit (%)		22		PI x 0.425 Ratio (%)		741.2	
Plastic Index (%)		17		LS x 0.425 Ratio (%)		327.0	
Linear Shrinkage (%)		7.5		Particle Size Dist. Moisture Content (%)		23.6	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 12 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6853	Location	TP26
Client Reference	-		1.1
Sampling Method	AS1289.1.2.1 CI 6.4b		1.2
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 10/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
26.5		98		
19.0		97		
13.2		94		
9.5		88		
6.7		80		
4.75		68		
2.36		50		
1.18		41		
0.425		36		
0.075		31		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		60		0.075/0.425 Fines Ratio		0.86	
Plastic Limit (%)		24		PI x 0.425 Ratio (%)		1284.7	
Plastic Index (%)		36		LS x 0.425 Ratio (%)		499.6	
Linear Shrinkage (%)		14.0		Particle Size Dist. Moisture Content (%)		13.3	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 13 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6854	Location	TP31
Client Reference	-		1.2
Sampling Method	AS1289.1.2.1 CI 6.4b		1.3
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
53.0		100		
37.5		96		
19.0		88		
13.2		82		
9.5		78		
6.7		72		
4.75		65		
2.36		49		
1.18		38		
0.425		27		
0.075		17		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		25		0.075/0.425 Fines Ratio		0.65	
Plastic Limit (%)		14		PI x 0.425 Ratio (%)		292.1	
Plastic Index (%)		11		LS x 0.425 Ratio (%)		185.9	
Linear Shrinkage (%)		7.0		Particle Size Dist. Moisture Content (%)		9.2	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 14 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6855	Location	TP32
Client Reference	-		2.4
Sampling Method	AS1289.1.2.1 CI 6.4b		2.5
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 8/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH			
19.0		100					
13.2		93					
9.5		88					
6.7		83					
4.75		76					
2.36		65					
1.18		56					
0.425		46					
0.075		33					

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		47		0.075/0.425 Fines Ratio		0.71	
Plastic Limit (%)		17		PI x 0.425 Ratio (%)		1395.0	
Plastic Index (%)		30		LS x 0.425 Ratio (%)		581.2	
Linear Shrinkage (%)		12.5		Particle Size Dist. Moisture Content (%)		21.8	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 15 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6856	Location	TP33
Client Reference	-		0.9
Sampling Method	AS1289.1.2.1 CI 6.4b		1.0
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 10/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
26.5		98		
19.0		97		
13.2		92		
9.5		88		
6.7		82		
4.75		74		
2.36		60		
1.18		51		
0.425		45		
0.075		28		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		34		0.075/0.425 Fines Ratio		0.64	
Plastic Limit (%)		14		PI x 0.425 Ratio (%)		894.6	
Plastic Index (%)		20		LS x 0.425 Ratio (%)		447.3	
Linear Shrinkage (%)		10.0		Particle Size Dist. Moisture Content (%)		13.5	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		Form ID: W85MCRP Rev 2

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 16 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6857	Location	TP35
Client Reference	-		0.9
Sampling Method	AS1289.1.2.1 CI 6.4b		1.0
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 22/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
19.0		100		
13.2		100		
9.5		100		
6.7		97		
4.75		84		
2.36		58		
1.18		43		
0.425		35		
0.075		23		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		36		0.075/0.425 Fines Ratio		0.68	
Plastic Limit (%)		19		PI x 0.425 Ratio (%)		588.2	
Plastic Index (%)		17		LS x 0.425 Ratio (%)		276.8	
Linear Shrinkage (%)		8.0		Particle Size Dist. Moisture Content (%)		14.9	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 17 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6858	Location	TP37
Client Reference	-		0.4
Sampling Method	AS1289.1.2.1 CI 6.4b		0.5
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 10/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH
19.0		100		
13.2		87		
9.5		83		
6.7		78		
4.75		68		
2.36		51		
1.18		43		
0.425		37		
0.075		22		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		23		0.075/0.425 Fines Ratio		0.60	
Plastic Limit (%)		14		PI x 0.425 Ratio (%)		333.0	
Plastic Index (%)		9		LS x 0.425 Ratio (%)		222.0	
Linear Shrinkage (%)		6.0		Particle Size Dist. Moisture Content (%)		8.8	
Shrinkage Observations	Cracking						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	Approved Signatory: Gurdeep Singh
			Form ID: W85MCRP Rev 2

QUALITY OF MATERIALS REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4111-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	24/08/2026 Page 18 of 18

Test Procedures	AS1289.3.6.1, AS1289.3.1.2, AS1289.3.2.1, AS1289.3.4.1, AS1289.2.1.1, AS1289.3.3.1		
Sample Number	21791/S/26-6860	Location	TP40
Client Reference	-		0.4
Sampling Method	AS1289.1.2.1 CI 6.4b		0.5
Sampled By	Client Supplied	Material Source	Client supplied/sampled
Date Sampled/Tested	20/07/2026 / 8/08/2026	Material Type	-
Drying Methods	PSD: / ATT:Air Dried	Material Description	-
Atterberg Preparation	Dry Sieved		

AS Sieve (mm)	Specification Minimum (%)	Percent Passing (%)	Specification Maximum (%)	PARTICLE SIZE DISTRIBUTION GRAPH 
19.0		100		
13.2		97		
9.5		94		
6.7		92		
4.75		90		
2.36		81		
1.18		73		
0.425		65		
0.075		36		

Test Result	Specification Minimum (%)	Result	Specification Maximum (%)	Test Result	Specification Minimum (%)	Result	Specification Maximum (%)
Liquid Limit (%)		38		0.075/0.425 Fines Ratio		0.56	
Plastic Limit (%)		24		PI x 0.425 Ratio (%)		912.8	
Plastic Index (%)		14		LS x 0.425 Ratio (%)		554.2	
Linear Shrinkage (%)		8.5		Particle Size Dist. Moisture Content (%)		19.7	
Shrinkage Observations	Curling						


Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory: Gurdeep Singh		
	Form ID: W85MCRP Rev 2		

CALIFORNIA BEARING RATIO REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4148-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	26/08/2026 Page 1 of 5

Test Procedures	AS1289.6.1.1, AS1289.1.1, AS1289.5.2.1, AS1289.2.1.1		
Sample Number	21791/S/26-6843	Location	TP08
Sampling Method	AS1289.1.2.1 CI 6.4b		0.3
Date Sampled	20/07/2026		0.4
Sampled By	Client Supplied		
Date Tested	21/08/2026	Prep Material > 53mm (%)	1
Material Source	Client supplied/sampled	Material Limit Start	-
Material Type	-	Material Limit End	-
Client Reference	-	Compactive Effort	Modified

Material Description	Insitu		
Maximum Dry Density (t/m³):	1.78	CBR PENETRATION PLOT 	
Optimum Moisture Content (%):	17.5		
Field Moisture Content (%):	13.6		
Sample Percent Oversize (%)	4.0		
Oversize Included / Excluded	Excluded		
Target Density Ratio (%):	95		
Target Moisture Ratio (%):	100		
Placement Dry Density (t/m³):	1.69		
Placement Dry Density Ratio (%):	95.0		
Placement Moisture Content (%):	17.9		
Placement Moisture Ratio (%):	102.5		
Test Condition / Soaking Period:	Soaked / 4 Days		
CBR Surcharge (kg)	4.5		
Dry Density After Soak (t/m³):	1.68		
Total Curing Time (hrs)	76		
Liquid Limit Method	Estimation		
Moisture (top 30mm) After Soak (%)	20.0		
Moisture (remainder) After Soak (%)	20.6		
CBR Swell (%):	0.5		
Minimum CBR Specification (%):	-		
CBR Value @ 5.0mm (%):	14		

Remarks


	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory:	Gurdeep Singh	
	Form ID:	W2ASRep Rev 3	

CALIFORNIA BEARING RATIO REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4148-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	26/08/2026 Page 2 of 5

Test Procedures	AS1289.6.1.1, AS1289.1.1, AS1289.5.2.1, AS1289.2.1.1		
Sample Number	21791/S/26-6844	Location	TP09
Sampling Method	AS1289.1.2.1 CI 6.4b		0.7
Date Sampled	20/07/2026		0.9
Sampled By	Client Supplied		
Date Tested	25/08/2026	Prep Material > 53mm (%)	-
Material Source	Client supplied/sampled	Material Limit Start	-
Material Type	-	Material Limit End	-
Client Reference	-	Compactive Effort	Modified

Material Description clayey with coffee rocks


Maximum Dry Density (t/m³):	2.15	CBR PENETRATION PLOT 
Optimum Moisture Content (%):	12.0	
Field Moisture Content (%):	11.8	
Sample Percent Oversize (%):	0.0	
Oversize Included / Excluded	Excluded	
Target Density Ratio (%):	95	
Target Moisture Ratio (%):	100	
Placement Dry Density (t/m³):	2.03	
Placement Dry Density Ratio (%):	94.5	
Placement Moisture Content (%):	11.9	
Placement Moisture Ratio (%):	99.0	
Test Condition / Soaking Period:	Soaked / 4 Days	
CBR Surcharge (kg)	4.5	
Dry Density After Soak (t/m³):	2.03	
Total Curing Time (hrs)	72	
Liquid Limit Method	Estimation	
Moisture (top 30mm) After Soak (%)	15.0	
Moisture (remainder) After Soak (%)	16.7	
CBR Swell (%):	0.5	
Minimum CBR Specification (%):	-	
CBR Value @ 2.5mm (%):	12	

Remarks

CALIFORNIA BEARING RATIO REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4148-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	26/08/2026 Page 3 of 5

Test Procedures	AS1289.6.1.1, AS1289.1.1, AS1289.5.2.1, AS1289.2.1.1		
Sample Number	21791/S/26-6846	Location	TP13
Sampling Method	AS1289.1.2.1 CI 6.4b		0.1
Date Sampled	20/07/2026		0.3
Sampled By	Client Supplied		
Date Tested	25/08/2026	Prep Material > 53mm (%)	2
Material Source	Client supplied/sampled	Material Limit Start	-
Material Type	-	Material Limit End	-
Client Reference	-	Compactive Effort	Modified

Material Description	Insitu		
Maximum Dry Density (t/m³):	2.12	CBR PENETRATION PLOT 	
Optimum Moisture Content (%):	10.0		
Field Moisture Content (%):	6.6		
Sample Percent Oversize (%):	19.0		
Oversize Included / Excluded	Excluded		
Target Density Ratio (%):	95		
Target Moisture Ratio (%):	100		
Placement Dry Density (t/m³):	2.02		
Placement Dry Density Ratio (%):	95.0		
Placement Moisture Content (%):	9.7		
Placement Moisture Ratio (%):	99.0		
Test Condition / Soaking Period:	Soaked / 4 Days		
CBR Surcharge (kg)	4.5		
Dry Density After Soak (t/m³):	2.02		
Total Curing Time (hrs)	25		
Liquid Limit Method	Estimation		
Moisture (top 30mm) After Soak (%)	11.6		
Moisture (remainder) After Soak (%)	10.9		
CBR Swell (%):	0.0		
Minimum CBR Specification (%):	-		
CBR Value @ 5.0mm (%):	35		

Remarks

	Accredited for compliance with ISO/IEC 17025 – Testing This report shall not be altered or reproduced, except in full.		
	Accreditation Number:	1986	
	Corporate Site Number:	21791	
	Approved Signatory:	Gurdeep Singh	
	Form ID:	W2ASRep Rev 3	

CALIFORNIA BEARING RATIO REPORT


Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4148-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	26/08/2026 Page 4 of 5

Test Procedures	AS1289.6.1.1, AS1289.1.1, AS1289.5.2.1, AS1289.2.1.1		
Sample Number	21791/S/26-6849	Location	TP18
Sampling Method	AS1289.1.2.1 CI 6.4b		0.2
Date Sampled	20/07/2026		0.4
Sampled By	Client Supplied		
Date Tested	25/08/2026	Prep Material > 53mm (%)	-
Material Source	Client supplied/sampled	Material Limit Start	-
Material Type	-	Material Limit End	-
Client Reference	-	Compactive Effort	Modified

Material Description natural gravel (clayey with coffee rocks)

Maximum Dry Density (t/m³):	1.98
Optimum Moisture Content (%):	13.0
Field Moisture Content (%):	11.3
Sample Percent Oversize (%):	4.0
Oversize Included / Excluded	Excluded
Target Density Ratio (%):	95
Target Moisture Ratio (%):	100
Placement Dry Density (t/m³):	1.88
Placement Dry Density Ratio (%):	95.0
Placement Moisture Content (%):	12.6
Placement Moisture Ratio (%):	98.5
Test Condition / Soaking Period:	Soaked / 4 Days
CBR Surcharge (kg)	4.5
Dry Density After Soak (t/m³):	1.87
Total Curing Time (hrs)	73
Liquid Limit Method	Estimation
Moisture (top 30mm) After Soak (%)	15.3
Moisture (remainder) After Soak (%)	16.2
CBR Swell (%):	0.5
Minimum CBR Specification (%):	-
CBR Value @ 2.5mm (%):	20

CBR PENETRATION PLOT



Remarks



Accredited for compliance with ISO/IEC 17025 – Testing
This report shall not be altered or reproduced, except in full.

Accreditation Number: 1986
Corporate Site Number: 21791



Approved Signatory: Gurdeep Singh
Form ID: W2ASRep Rev 3


CALIFORNIA BEARING RATIO REPORT

Client:	CMW Geosciences Pty Ltd	Report Number:	21791/R/26-4148-1
Client Address:	Suite 1, Level 3, 29 Flynn Street, Wembley	Project Number:	21791/P/25-2
Project:	FY2025 Darwin & Surrounding Areas (CMW)	Lot Number:	
Location:	Darwin	Internal Test Request:	21791/T/26-1403
Component:	Quality Testing	Client Reference/s:	DAR2026-0015
Area Description:		Report Date / Page:	26/08/2026 Page 5 of 5

Test Procedures	AS1289.6.1.1, AS1289.1.1, AS1289.5.2.1, AS1289.2.1.1		
Sample Number	21791/S/26-6851	Location	TP22
Sampling Method	AS1289.1.2.1 CI 6.4b		0.2
Date Sampled	20/07/2026		0.4
Sampled By	Client Supplied		
Date Tested	25/08/2026	Prep Material > 53mm (%)	-
Material Source	Client supplied/sampled	Material Limit Start	-
Material Type	-	Material Limit End	-
Client Reference	-	Compactive Effort	Modified

Material Description natural gravel (silty with coffee rocks)

Maximum Dry Density (t/m³):	2.03
Optimum Moisture Content (%):	12.0
Field Moisture Content (%):	8.9
Sample Percent Oversize (%)	0.0
Oversize Included / Excluded	Excluded
Target Density Ratio (%):	95
Target Moisture Ratio (%):	100
Placement Dry Density (t/m³):	1.94
Placement Dry Density Ratio (%):	95.5
Placement Moisture Content (%):	11.8
Placement Moisture Ratio (%):	99.0
Test Condition / Soaking Period:	Soaked / 4 Days
CBR Surcharge (kg)	4.5
Dry Density After Soak (t/m³):	1.94
Total Curing Time (hrs)	25
Liquid Limit Method	Estimation
Moisture (top 30mm) After Soak (%)	13.7
Moisture (remainder) After Soak (%)	14.3
CBR Swell (%):	0.0
Minimum CBR Specification (%):	-
CBR Value @ 5.0mm (%):	35



Remarks




Darwin

Unit 3
4 Berrimah Road Berrimah NT 0828
Australia

Ph: +61 8 8947 2780

www.cmwgeosciences.com


Appendix Three: Preliminary Civil Design Drawings



NOTES

- 1. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED IN COORDINATION WITH GEOTECHNICAL INVESTIGATIONS AND FLOOD AND HYDROLOGY ASSESSMENTS. DESIGN TO BE REFINED DURING DETAILED DESIGN AND DEVELOPMENT, INCLUDING GRADING AND ACCEPTABLE INTERFACE BETWEEN LOTS AND VERGES.
- 2. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED TO GAIN AN OVERARCHING UNDERSTANDING OF APPROXIMATE EARTHWORKS LEVELS, GRADING AND CUT AND FILL QUANTITIES TO ACHIEVE EFFICIENT AND COMPLIANT DESIGN. THIS HAS BEEN ACHIEVED BY TRIANGULATING ACROSS MULTIPLE DEVELOPMENT LOTS AND GRADING TOWARDS ROADWAYS AT APPROXIMATELY 1%, WHICH RESULTS IN CROSSFALL ACROSS LOTS GREATER THAN 2% IN SEVERAL LOCATIONS DUE TO ROAD GRADES. DURING DETAILED DESIGN, BATTERS BETWEEN LOTS IN ACCORDANCE WITH CITY OF PALMERSTON AND NTG REQUIREMENTS WILL BE INTRODUCED IN ORDER TO ENSURE A MAXIMUM GRADE OF 2% ACROSS LOTS IS ACHIEVED.
- 3. EARTHWORKS TO BE COMPLETED IN ACCORDANCE WITH NORTHERN TERRITORY SUBDIVISION GUIDELINES AND REFERENCED STANDARDS, ALONG WITH THE SITE SPECIFIC PROJECT GEOTECHNICAL REPORT BY CMW GEOSCIENCES, REF DAR2026-0015AB.
- 4. THERE IS EXPECTED TO BE ROCK MATERIAL PRESENT WITHIN CUT THAT IS ANTICIPATED TO BE SUITABLE FOR IN-SITU FILL PROVIDED IT IS CRUSHED AND TREATED IN ACCORDANCE WITH THE SITE PREPARATION AND METHODOLOGY AS INCLUDED IN THE GEOTECHNICAL REPORT.
- 5. IMPORTED FILL MAY BE NECESSARY FOR THE SITE, HOWEVER LIKELY TO BE MINIMISED OR AVOIDED DURING SUBSEQUENT EARTHWORKS DESIGN.
- 6. IN ACCORDANCE WITH THE GEOTECHNICAL REPORT, THE SITE IS NOTED TO BE SUITABLE FOR RESIDENTIAL DEVELOPMENT, WITH SITE CLASSIFICATION NOTED TO BE S CLASS IN ACCORDANCE WITH AS3798, PROVIDED EARTHWORKS AND SITE PREPARATION IS COMPLETED IN ACCORDANCE WITH THE GEOTECHNICAL REPORT.
- 7. THERE MAY BE CLAY MATERIAL PRESENT WITHIN THE LOWER LYING DRAINAGE BASIN AREAS, TO BE FURTHER INVESTIGATED AND COORDINATED WITH FINISHED DESIGN LEVELS. TREATMENT OF THIS MATERIAL OR SUITABLE REUSE TO BE FURTHER CONSIDERED AND DETERMINED.
- 8. ALL COMPLETED EARTHWORKS TO BE VERIFIED BY THE PROJECT GEOTECHNICAL ENGINEER UNDER LEVEL 1 GEOTECHNICAL SUPERVISION AS REQUIRED.

LEGEND



INDICATIVE CUT VOLUME: 188,000m³
INDICATIVE FILL VOLUME: 185,000m³

EARTHWORKS VOLUMES ARE RAW VOLUMES ESTIMATED FROM FINISHED SURFACE TO EXISTING NATURAL SURFACE. EARTHWORKS FILL IS NOTED AS BANK CUBIC METRES WITH FILL IN A COMPACTED STATE.


NO ALLOWANCE HAS BEEN CONSIDERED FOR BULKING OR COMPACTION FACTORS IN ORDER TO DETERMINE ANY DISCREPANCIES BETWEEN CUT AND FILL AND ESTIMATION OF ANY ADDITIONAL FILL THAT MAY BE REQUIRED. THIS SHALL BE REVIEWED AND REFINED AS PART OF DETAILED DESIGN AND IN DISCUSSION WITH THE PROJECT GEOTECHNICAL ENGINEER.

NO ALLOWANCE HAS BEEN MADE FOR REMOVAL OF UNSUITABLE MATERIAL FROM SITE.

LAYOUT PLAN

SCALE 1:2000 0m 40m 80m

FILE PATH: C:\1205 WORKSPACE\DATA\17182 LARRAKIA DEVELOPMENT CORPORATION_5657\00170 DRG\DEVELOPMENT APPLICATION\17182-DA-C1-EW-01



Larrakia
Development
Corporation



DEVELOPMENT APPLICATION


DATE	SEPTEMBER 2026	GRD	MG94-Z-52	DATUM	AHD
DESIGNED	PO	DRAWN	PO	CHECKED	JC
NT DCA	-	SCALE	1:2000	@	A1

LARRAKIA DEVELOPMENT CORPORATION
FARRAR WEST DEVELOPMENT

EARTHWORKS
OVERALL EARTHWORKS CUT & FILL PLAN

17182-DA-C1-EW-01

A




- NOTES**
1. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED IN COORDINATION WITH GEOTECHNICAL INVESTIGATIONS AND FLOOD AND HYDROLOGY ASSESSMENTS. DESIGN TO BE REFINED DURING DETAILED DESIGN AND DEVELOPMENT, INCLUDING GRADING AND ACCEPTABLE INTERFACE BETWEEN LOTS AND VERGES.
 2. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED TO GAIN AN OVERARCHING UNDERSTANDING OF APPROXIMATE EARTHWORKS LEVELS, GRADING AND CUT AND FILL QUANTITIES TO ACHIEVE EFFICIENT AND COMPLIANT DESIGN. THIS HAS BEEN ACHIEVED BY TRIANGULATING ACROSS MULTIPLE DEVELOPMENT LOTS AND GRADING TOWARDS ROADWAYS AT APPROXIMATELY 1%, WHICH RESULTS IN CROSSFALL ACROSS LOTS GREATER THAN 2% IN SEVERAL LOCATIONS DUE TO ROAD GRADES. DURING DETAILED DESIGN, BATTERS BETWEEN LOTS IN ACCORDANCE WITH CITY OF PALMERSTON AND NTG REQUIREMENTS WILL BE INTRODUCED IN ORDER TO ENSURE A MAXIMUM GRADE OF 2% ACROSS LOTS IS ACHIEVED.
 3. EARTHWORKS TO BE COMPLETED IN ACCORDANCE WITH NORTHERN TERRITORY SUBDIVISIONAL GUIDELINES AND REFERENCED STANDARDS, ALONG WITH THE SITE SPECIFIC PROJECT GEOTECHNICAL REPORT BY CMW GEOSCIENCES, REF DAR2026-0015AB.
 4. THERE IS EXPECTED TO BE ROCK MATERIAL PRESENT WITHIN CUT THAT IS ANTICIPATED TO BE SUITABLE FOR IN-SITU FILL PROVIDED IT IS CRUSHED AND TREATED IN ACCORDANCE WITH THE SITE PREPARATION AND METHODOLOGY AS INCLUDED IN THE GEOTECHNICAL REPORT.
 5. IMPORTED FILL MAY BE NECESSARY FOR THE SITE, HOWEVER LIKELY TO BE MINIMISED OR AVOIDED DURING SUBSEQUENT EARTHWORKS DESIGN.
 6. IN ACCORDANCE WITH THE GEOTECHNICAL REPORT, THE SITE IS NOTED TO BE SUITABLE FOR RESIDENTIAL DEVELOPMENT, WITH SITE CLASSIFICATION NOTED TO BE S CLASS IN ACCORDANCE WITH AS3798, PROVIDED EARTHWORKS AND SITE PREPARATION IS COMPLETED IN ACCORDANCE WITH THE GEOTECHNICAL REPORT.
 7. THERE MAY BE CLAY MATERIAL PRESENT WITHIN THE LOWER LYING DRAINAGE BASIN AREAS, TO BE FURTHER INVESTIGATED AND COORDINATED WITH FINISHED DESIGN LEVELS. TREATMENT OF THIS MATERIAL OR SUITABLE REUSE TO BE FURTHER CONSIDERED AND DETERMINED.
 8. ALL COMPLETED EARTHWORKS TO BE VERIFIED BY THE PROJECT GEOTECHNICAL ENGINEER UNDER LEVEL 1 GEOTECHNICAL SUPERVISION AS REQUIRED.

LAYOUT PLAN
SCALE 1:2000 0m 40m 80m

REV	DATE	DESCRIPTION	BY	CHKR	REV	DATE	DESCRIPTION	BY	CHKR
A	25/09/2026	DEVELOPMENT APPLICATION ISSUE	PO	FO					



DRAWING STATUS				CLIENT			
DEVELOPMENT APPLICATION				LARRAKIA DEVELOPMENT CORPORATION FARRAR WEST DEVELOPMENT			
DATE SEPTEMBER 2026		GRID MGA94-Z 52		DATUM AHD		TITLE EARTHWORKS STAGE 1 PLAN	
DESIGNED PO	DRAWN PO	CHECKED JC	APPROVED FO	SHEET SIZE A1		DRG No. 17182-DA-C1-EW-02	
NT D.C.A.				SCALE U.N.O. 1:2000 @		REVISION A	



1. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED IN COORDINATION WITH GEOTECHNICAL INVESTIGATIONS AND FLOOD AND HYDROLOGY ASSESSMENTS. DESIGN TO BE REFINED DURING DETAILED DESIGN AND DEVELOPMENT, INCLUDING GRADING AND ACCEPTABLE INTERFACE BETWEEN LOTS AND VERGES.
2. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED TO GAIN AN OVERARCHING UNDERSTANDING OF APPROXIMATE EARTHWORKS LEVELS, GRADING AND CUT AND FILL QUANTITIES TO ACHIEVE EFFICIENT AND COST EFFECTIVE DESIGN. DESIGN HAS BEEN ACHIEVED BY TRIANGULAR GRADING ACROSS MULTIPLE DEVELOPMENT LOTS AND GRADING TOWARDS ROADWAYS AT APPROXIMATELY 1%, WHICH RESULTS IN CROSSFALL ACROSS LOTS GREATER THAN 2% IN SEVERAL LOCATIONS DUE TO ROAD GRADES. DURING DETAILED DESIGN, BATTERS BETWEEN LOTS IN ACCORDANCE WITH CITY OF PALMERSTON AND NTG REQUIREMENTS WILL BE INTRODUCED IN ORDER TO ENSURE A MAXIMUM GRADE OF 0.2% ACROSS LOTS IS ACHIEVED.
3. EARTHWORKS TO BE COMPLETED IN ACCORDANCE WITH NORTHERN TERRITORY SUBDIVISIONAL GUIDELINES AND REFERENCED STANDARDS, ALONG WITH THE SITE SPECIFIC PROJECT GEOTECHNICAL REPORT BY CMW GEOSCIENCES, REF DAR20260015AB.
4. THERE IS EXPECTED TO BE ROCK MATERIAL PRESENT WITHIN CUT THAT IS ANTICIPATED TO BE SUITABLE FOR IN-SITU FILL PROVIDED IT IS CRUSHED AND TREATED IN ACCORDANCE WITH THE SITE PREPARATION AND METHODOLOGY AS INCLUDED IN THE GEOTECHNICAL REPORT.
5. IMPORTED FILL MAY BE NECESSARY FOR THE SITE, HOWEVER LIKELY TO BE MINIMISED OR AVOIDED DURING SUBSEQUENT EARTHWORKS DESIGN.
6. IN ACCORDANCE WITH THE GEOTECHNICAL REPORT, THE SITE IS NOTED TO BE SUITABLE FOR RESIDENTIAL DEVELOPMENT, WITH SITE CLASSIFICATION NOTED TO BE A CLASS IN ACCORDANCE WITH AS3798, PROVIDED EARTHWORKS AND SITE PREPARATION IS COMPLETED IN ACCORDANCE WITH THE GEOTECHNICAL REPORT.
7. THERE MAY BE CLAY MATERIAL PRESENT WITHIN THE LOWER LYING DRAINAGE BASIN AREAS, TO BE FURTHER INVESTIGATED AND COORDINATED WITH FINISHED DESIGN LEVELS. TREATMENT OF THIS MATERIAL, OR SUITABLE REUSE TO BE FURTHER CONSIDERED AND DETERMINED.
8. ALL COMPLETED EARTHWORKS TO BE VERIFIED BY THE PROJECT GEOTECHNICAL ENGINEER UNDER LEVEL 1 GEOTECHNICAL SUPERVISION AS REQUIRED.




LAYOUT PLAN

SCALE 1:2000 0m 40m 80m

[illegible]


FILE PATH: C:\12DS WORKSPACE\DATA\UAMELSQL01\17-182 LARRAKIA DEVELOPMENT CORPORATION_5657\CI\W70 DRG\DEVELOPMENT APPLICATION\17182-DA-C1-EW-03



1. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED IN COORDINATION WITH GEOTECHNICAL INVESTIGATIONS AND FLOOD AND HYDROLOGY ASSESSMENTS. DESIGN TO BE REFINED DURING DETAILED DESIGN AND DEVELOPMENT, INCLUDING GRADING AND ACCEPTABLE INTERFACE BETWEEN LOTS AND VERGES.
2. PRELIMINARY EARTHWORKS DESIGN HAS BEEN COMPLETED TO GAIN AN OVERARCHING UNDERSTANDING OF APPROXIMATE EARTHWORKS LEVELS, GRADING AND CUT AND FILL QUANTITIES TO ACHIEVE EFFICIENT AND COST EFFECTIVE DESIGN. DESIGN HAS BEEN ACHIEVED BY TRIANGULAR GRADING ACROSS MULTIPLE DEVELOPMENT LOTS AND GRADING TOWARDS ROADWAYS AT APPROXIMATELY 1%, WHICH RESULTS IN CROSSFALL ACROSS LOTS GREATER THAN 2% IN SEVERAL LOCATIONS DUE TO ROAD GRADES. DURING DETAILED DESIGN, BATTERS BETWEEN LOTS IN ACCORDANCE WITH CITY OF PALMERSTON AND NTG REQUIREMENTS WILL BE INTRODUCED IN ORDER TO ENSURE A MAXIMUM GRADE OF 0.2% ACROSS LOTS IS ACHIEVED.
3. EARTHWORKS TO BE COMPLETED IN ACCORDANCE WITH NORTHERN TERRITORY SUBDIVISIONAL GUIDELINES AND REFERENCED STANDARDS, ALONG WITH THE SITE SPECIFIC PROJECT GEOTECHNICAL REPORT BY CMW GEOSCIENCES, REF DAR20260015A8.
4. THERE IS EXPECTED TO BE ROCK MATERIAL PRESENT WITHIN CUT THAT IS ANTICIPATED TO BE SUITABLE FOR IN-SITU FILL PROVIDED IT IS CRUSHED AND TREATED IN ACCORDANCE WITH THE SITE PREPARATION AND METHODOLOGY AS INCLUDED IN THE GEOTECHNICAL REPORT.
5. IMPORTED FILL MAY BE NECESSARY FOR THE SITE, HOWEVER LIKELY TO BE MINIMISED OR AVOIDED DURING SUBSEQUENT EARTHWORKS DESIGN.
6. IN ACCORDANCE WITH THE GEOTECHNICAL REPORT, THE SITE IS NOTED TO BE SUITABLE FOR RESIDENTIAL DEVELOPMENT, WITH SITE CLASSIFICATION NOTED TO BE A CLASS IN ACCORDANCE WITH AS3798, PROVIDED EARTHWORKS AND SITE PREPARATION IS COMPLETED IN ACCORDANCE WITH THE GEOTECHNICAL REPORT.
7. THERE MAY BE CLAY MATERIAL PRESENT WITHIN THE LOWER LYING DRAINAGE BASIN AREAS, TO BE FURTHER INVESTIGATED AND COORDINATED WITH FINISHED DESIGN LEVELS. TREATMENT OF THIS MATERIAL, OR SUITABLE REUSE TO BE FURTHER CONSIDERED AND DETERMINED.
8. ALL COMPLETED EARTHWORKS TO BE VERIFIED BY THE PROJECT GEOTECHNICAL ENGINEER UNDER LEVEL 1 GEOTECHNICAL SUPERVISION AS REQUIRED.

SCALE 1:2000 0m 40m 80m

EARTHWORKS STAGE 3. APPROXIMATELY 15,000m³ to 20,000m³ FILL. IMPORT FILL MAY BE NECESSARY, HOWEVER INTENT TO REFINES EARTHWORKS TO AVOID OR MINIMISE IMPORT FILL.


[illegible]

Larrakia
Development
Corporation




DRAWING STATUS				CLIENT & JOB			
DEVELOPMENT APPLICATION				LARRAKIA DEVELOPMENT CORPORATION FARRAR WEST DEVELOPMENT			
DATE		GRID		DATUM		TITLE	
SEPTEMBER 2026		MGA94-Z 52		AHD		EARTHWORKS STAGE 3 PLAN	
DESIGNED		APPROVED					
PO	PRO	CHECKED	FO	 /			
MT D C A		SCALE (1) N.O.		SHEET SIZE		ORIG No.	
-		1:2000 @		A1		17182-DA-C1-EW-04	
						REVISION	
						A	


FILE PATH: C:\12DS- WORKSPACE\DATA\MAJELSQU117-182_LARRAKIA DEVELOPMENT CORPORATION_5657QV70 DRG\DEVELOPMENT APPLICATION\17182-DA-C1-EX-01




SECTION A PROFILE
SCALE HOR 1:500
VER 1:200




SECTION B PROFILE
SCALE HOR 1:500
VER 1:200




SECTION C PROFILE
SCALE HOR 1:500
VER 1:200




SECTION D PROFILE
SCALE HOR 1:500
VER 1:200




SECTION E PROFILE
SCALE HOR 1:500
VER 1:200




SECTION F PROFILE
SCALE HOR 1:500
VER 1:200



SECTION G PROFILE
SCALE HOR 1:500
VER 1:200



SECTION H PROFILE
SCALE HOR 1:500
VER 1:200



SECTION G PROFILE
SCALE HOR 1:500
VER 1:200


HOR. SCALE 1:500
VER. SCALE 1:200

REV	DATE	DESCRIPTION	BY	CHKR	REV	DATE	DESCRIPTION	BY	CHKR
A	25/09/2026	DEVELOPMENT APPLICATION ISSUE	PO	FO					




DRAWING STATUS				CLIENT & JOB	
DEVELOPMENT APPLICATION				LARRAKIA DEVELOPMENT CORPORATION FARRAR WEST DEVELOPMENT	
DATE	SEPTEMBER 2026	GRD	MDA94-Z 52	DATUM	AHD
DESIGNED	PO	DRAWN	PO	CHECKED	JC
INT'D C.A.	-	SCALE	U.N.D.	SHEET SIZE	A1
AS SHOWN @				GRD No.	17182-DA-C1-EX-01
					REVISION
					A


FILE PATH: C:\12DS- WORKSPACE\DATA\MAJELSQL\117-182 LARRAKIA DEVELOPMENT CORPORATION_5657\QV70 DRG\DEVELOPMENT APPLICATION\17182-DA-C1-EX-01



SECTION J PROFILE 
SCALE HOR 1:500
VER 1:200





SECTION J PROFILE (CONT.) 
SCALE HOR 1:500
VER 1:200



SECTION K PROFILE 
SCALE HOR 1:500
VER 1:200

HOR. SCALE 1:500
VER. SCALE 1:200



Larrakia
Development
Corporation



DRAWING STATUS

DEVELOPMENT APPLICATION

DATE SEPTEMBER 2026

GRD MGA94-Z 52

DATUM AHD

DESIGNED PO

DRAWN PO

CHECKED JC

APPROVED FO

FO

INT'D C.A.

SCALE I.N.D.

AS SHOWN @

CLIENT & JOB

LARRAKIA DEVELOPMENT CORPORATION
FARRAR WEST DEVELOPMENT

TITLE

EARTHWORKS
CROSS SECTIONS - SHEET 2

SHEET SIZE

GRD No.

17182-DA-C1-EX-02

REVISION

A

REV DATE

DESCRIPTION

BY

CHKR


REV

DATE

DESCRIPTION

BY


CHKR



LEGEND


- PROPOSED STORMWATER AND ASSOCIATED PITS
- EXISTING STORMWATER AND ASSOCIATED PITS
- PROPOSED SEWER AND ASSOCIATED CHAMBERS (DN150 U.S.O.)
- EXISTING SEWER AND ASSOCIATED CHAMBERS
- PROPOSED WATER AND ASSOCIATED FITTINGS
- EXISTING WATER AND ASSOCIATED FITTINGS
- PROPOSED WATER CONNECTION
- PROPOSED COMMUNICATIONS CONDUIT AND ASSOCIATED PITS
- EXISTING COMMUNICATIONS CONDUIT AND ASSOCIATED PITS
- PROPOSED HIGH VOLTAGE POWER CABLE
- PROPOSED LOW VOLTAGE POWER CABLE AND ASSOCIATED PITS
- EXISTING POWER AND CONDUIT AND ASSOCIATED PITS
- PROPOSED ELECTRICAL DOMES AND EXCLUSION ZONE
- PROPOSED STREET LIGHT
- CATCHMENT [EPs]
- EXISTING SEWER TO BE ABANDONED

CUMULATIVE NODE DEMAND



LAYOUT PLAN

SCALE 1:2000 0m 40m 80m



Larrakia
Development
Corporation



DEVELOPMENT APPLICATION


DATE SEPTEMBER 2026 GRD MGA94-Z 52 DATUM AHD
DESIGNED PO DRAWN PO CHECKED JC APPROVED FO
NT DCA SCALE 1:2000 @

LARRAKIA DEVELOPMENT CORPORATION
FARRAR WEST DEVELOPMENT

TITLE
SEWER LAYOUT PLAN
OVERALL LAYOUT

SHEET SIZE A1 GRD No 17182-DA-C2-SD-01

REVISION
A




SCALE 1:2000 0m 40m 80m

REVISIONS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
-----------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



DRAWING STATUS				CLIENT & JOB	
DEVELOPMENT APPLICATION				LARRAKIA DEVELOPMENT CORPORATION FARRAR WEST DEVELOPMENT	
DATE		GRID	DATUM	TITLE	
SEPTEMBER 2026		MG94-Z 52	AHD	SEWER LAYOUT PLAN STAGE 1 AND 2	
DESIGNED	DRAWN	CHECKED	APPROVED		
PO	PO	JC	PO	/ ...	
MT D.C.A.		SCALE 1:1000	SHEET SIZE	SHEET NO.	REVISION
-		@	A1	17182-DA-C2-SD-02	A

1. DRAWING TO BE READ IN CONJUNCTION WITH STORMWATER MANAGEMENT PLAN - PART 1
2. CATCHMENTS ESTIMATED FROM LIDAR INFORMATION AND PREVIOUS REPORTING PROVIDED BY DLI.

[illegible]